

NTPC LTD

SECTION-II QR & SOW

ENLISTMENT OF VENDORS FOR TRANSPORTATION OF ASH THROUGH ROAD FROM NTPC PLANTS TO VARIOUS DESTINATIONS

1.) REF NO.	WR-I SSC-C&M-0002-(CEG AST-01)
2.) NAME OF WORK	TRANSPORTATION OF ASH THROUGH ROAD FROM NTPC PLANTS TO VARIOUS DESTINATIONS
3.) NAME OF PROJECT / STATION	NTPC Plants
4.) BRIEF DESCRIPTION AND SCOPE OF WORK	<p>NTPC invites applications from eligible vendors for enlistment to be used for the future tenders of Transportation of ash through road from various NTPC plants to different destinations such as Road Projects, Flyover Embankments, Mines, Shoreline Protection Structures, Dam Construction, or any other destination as per the requirement of specific tenders having scope of work as brought out below. The enlisted eligible vendors shall be considered for the various tenders as per their execution capability defined under enlistment document hereafter.</p> <p>Further, the enlisted vendor(s) shall be considered for execution of the value of work up to INR 50 Crore under a future tender as per their qualification established under the process of enlistment.</p> <p>The scope of work of NTPC tenders will generally include Transportation of ash through road from various NTPC plants to different destinations of Ash utilization Avenues such as Road Projects, Flyover Embankments, Mines, Shoreline Protection Structures, Dam Construction, or any other destination as per requirement, including work of excavation, Loading of ash from Ash Dyke/Ash Silo of NTPC thermal power plant(s) by mechanical means, Transporting ash in a closed container / dumpers (Covered with tarpaulin) as per CPCB guidelines, Unloading and stacking (if required) at various destinations as per the requirement of specific tenders and complying to statutory norms and government rules.</p> <p>Suitable arrangements have to be made by the Agency for transportation of ash in an environmentally friendly manner. Agency has to ensure that no spillage of ash takes place during transportation. Ash is to be collected from NTPC plants as per availability on as-is-where-is basis. The Agency has to unload the ash throughout the stretch / length of road and other designated areas as indicated in the scope of work for specific tenders.</p>